

# COLERAINE BOROUGH COUNCIL

## *Northern Ireland Water Capital Works Presentation 2008/09*

### Projects under Construction or Programmed to Commence this Financial Year (April 2008 & March 2009)

	<u>Project Name</u>	<u>Description</u>	<u>Cost</u>	<u>Status</u>
1	Portballintrae Zone Watermain Improvements	Watermains Rehabilitation Programme- Construction phase 2 of work identified in the detailed zone study.	£2,243,000	Construction
2	Portballintrae Zone Watermain Improvements	Water Mains Rehabilitation Programme - Construction phase 1 of work identified in the detailed zone study.	£2,059,000	Maintenance
3	Portrush Sewer Improvements Stage 4	The closure of a number of combined storm overflows located throughout Portrush and the upsizing of a number of sections of the combined sewers.	£1,192,000	Substantially Complete
4	Moneygran Road Kilrea Foul and Storm Sewers	Provision of 100m of 375mm diameter storm sewer and 220m of 450mm diameter foul relief sewer to serve new development.	£0	Design

Approve expenditure total: £5,494,000

## Projects Scheduled to Start in the Next Two Financial Years (April 2009 & March 2011)

	<u>Project Name</u>	<u>Description</u>	<u>Cost</u>	<u>Status</u>
5	Shanlongford Ringsend Sewerage Scheme	Construction of a foul sewer along with replacement wastewater treatment works to provide time service 17 properties.	N/A	Feasibility
6	Coleraine Drainage Area Plan	Civil works arising from Drainage Area Study	N/A	Feasibility
7	Garvagh Drainage Area Plan	Civil works arising from drainage area study	N/A	Feasibility
8	Ballinrees Central Zone Watermain Improvements	Water Mains Rehabilitation Programme - construction phase of detailed zone study.	N/A	Design
9	Ballinrees East Zone Watermain Improvements	Water Mains Rehabilitation Programme - construction phase of detailed zone study.	N/A	Feasibility