

COOKSTOWN DISTRICT COUNCIL AREA

Northern Ireland Water Capital Works Presentation 2008/09

Projects under Construction or Programmed to Commence this Financial Year (April 2008 & March 2009)

	<u>Project Name</u>	<u>Description</u>	<u>Cost</u>	<u>Status</u>
1	Cookstown Wastewater Treatment Works	Replacement and upgrading of existing wastewater treatment works.	£12,771,000	Substantially Complete
2	Pomeroy Wastewater Treatment Works	Upgrading of wastewater treatment works to ensure compliance with consent and to cater for future development.	£2,803,000	Substantially Complete
3	Cookstown Zone Water Main Improvements	Water mains rehabilitation programme - construction phase of detailed zone study	£2,012,000	Construction
4	Chapel Street, Cookstown	Provision of 250m of 450mm diameter storm sewer to alleviate out of sewer flooding and serve a new housing development in Chapel Street area.	£330,000	Construction
5	Turnaface Road Moneymore	Upgrade of existing sewage pumping station.	£87,000	Construction
6	Mullanahoe Road Ardboe Foul Sewer	Provision of 550m of 150mm diameter foul sewer to serve existing and new development.	£64,000	Maintenance
7	Cookstown Road Moneymore Foul Sewer Extension	Provision of 150mm diameter foul sewer extension to serve existing development.	£31,000	Maintenance
8	Dunmore Lane, Cookstown, Water Main Extension	Provision of 600 m of 125 mm diameter water main extension main to serve existing and proposed development.	£29,000	Maintenance
9	Milburn Storm Sewer	Provision of 58m of 375mm diameter concrete storm sewer to serve new development.	£11,000	Maintenance
10	Church Street, Cookstown	Provision of 75m of 250mm diameter foul sewer and 75m of 300mm diameter storm sewer to serve a new development.	N/A	Feasibility
11	Lissan Road Cookstown Replacement Storm Sewer	Replacement of defective section of 600mm and 525mm diameter storm sewer.	N/A	Feasibility

Projects under Construction or Programmed to Commence this Financial Year (April 2008 & March 2009)

	<u>Project Name</u>	<u>Description</u>	<u>Cost</u>	<u>Status</u>
12	Coolreaghs Road, Cookstown Storm Sewer	Provision of storm sewer to serve a new development.	N/A	

Sub total: £18,138,000

Projects Scheduled to Start in the Next Two Financial Years (April 2009 & March 2011)

	<u>Project Name</u>	<u>Description</u>	<u>Cost</u>	<u>Status</u>
13	Money more Wastewater Treatment Works Improvements	Upgrading of Wastewater Treatment Works to ensure compliance with consent and cater for future development	N/A	Feasibility
14	Stewartstown Wastewater Treatment Works Improvements	Upgrade works on existing site at Stewartstown	N/A	Design Complete
15	Coagh Wastewater Treatment Works Improvements	Upgrading of wastewater treatment works to ensure compliance with consent and to cater for future development	N/A	Feasibility
16	Money more Drainage Area Plan	Capital works arising out of the Drainage Area Study	N/A	Feasibility
17	Cookstown Drainage Area Plan	Capital Works arising from currently ongoing drainage area study	N/A	Feasibility
18	Westland Road, Cookstown - Sewage Pumping Station Upgrade	Replacement of the existing sewage pumping station and pumping main in order to eliminate instances of out of sewer flooding.	N/A	Feasibility
19	South Cookstown Sewer Network Improvements	Improvements to the sewer network to minimise instances of out of sewer flooding and	N/A	Feasibility